



DOOR SCHEDULE					
Door Number	Room Name	Room Number	Phase Created	Notes	Type Comments
101A	RECEPTION	101	Existing		TEMPERED GLAZING
102A	MEETING ROOM	102	1st Phase	2'-10"x6'-8" MIN	
103A	OPEN OFFICE	103	Existing		TEMPERED GLAZING
105A	OFFICE	105	1st Phase	2'-10"x6'-8" MIN	TEMPERED GLAZING
106A	OFFICE	106	2'-10"x6'-8" MIN		TEMPERED GLAZING
107A	OFFICE	107	1st Phase	2'-10"x6'-8" MIN	TEMPERED GLAZING
108A	OFFICE	108	1st Phase	2'-10"x6'-8" MIN	TEMPERED GLAZING
109A	RESTROOM	109	1st Phase	2'-10"x6'-8" MIN	

SIMPLIFIED WALL SCHEDULE				
Type Mark	Type	Length	Phase Created	Comments
EX - 1H	EXISTING 1HR WALL	145' - 4 1/2"	Existing	
EX	EXISTING STORFRONT	41' - 8"	Existing	
EX	EXISTING WALL	13' - 2"	Existing	
WB&OF	INT. WB&OF - (5/8 GYP - 2X4 WOOD(BATT) - 5/8 GYP)	84' - 10 15/16"	1st Phase	
SE-1	PRE-FABRICATED GLASS WALL	69' - 2"	1st Phase	TEMPERED GLAZING